




LEAHI HOSPITAL
HAWAII HEALTH SYSTEMS CORPORATION

3675 Kilauea Avenue ■ Honolulu, Hawaii 96816 ■ Telephone: (808) 733-8000

May 30, 2018

TO: Interested Bidders

FROM: Michelle Kato 
Contract Manager

SUBJECT: Addendum No. 2
IFB No. 18-007 Leahi Hospital- Young Basement Renovation

Addendum No. 2 extends the deadline for a second time and provides responses to RFIs.

1. **The bid deadline is extended to June 4, 2018 up to 2:00 p.m.**
2. **Please provide specifications for new solid surface countertops and splash.**
Response: See attached Exhibit A
3. **Answer to #6 in addendum #1 that requested a finish schedule was to “see Architectural Drawings”. I could not find a finish schedule. Please provide.**
Response: See attached Exhibit A
4. **Answer to #10 in addendum #1 which I believe was to provide a finish hardware schedule was “confirm only door hardware”. Please provide a hardware schedule. Or do we only provide the hinges described on sheet A-7?**
Response: See attached Exhibit A

END OF ADDENDUM NO. 2

DOOR HARDWARE LISTING

D.1 HW GROUP AT ALL DOORS UNLESS OTHERWISE NOTED

3.0	EA	HINGE	TA2314	4.5 X 4.5	US10B	MCK
1.0	EA	OFFICE LOCK	21-28-7G05	LG	US10B WBX	SAR
1.0	EA	DOOR CLOSER	1431	P9	EB	SAR
1.0	EA	FLOOR STOP	441H	613		ROC

D.1 HW GROUP AT TOILET DOORS

3.0	EA	HINGE	TA2314	4.5 X 4.5	US10B	MCK
1.0	EA	PRIVACY SET	49-8266	CRG	US10B WBX W/ INDICATOR	SAR
1.0	EA	KICK PLATE	K1050	10" X 34"	613	ROC
1.0	EA	FLOOR STOP	441H	613		ROC
1.0	EA	DOOR CLOSER	1431	P9	EB	SAR

D.2 HW GROUP AT DOORS AT CARPENTER'S SUPPLY ROOM AND LAUNDRY/FOLDING ROOM

6.0	EA	HINGE	TA2714	4.5 X 4.5	US10B	MCK
1.0	EA	OFFICE LOCK	28-10G05	LG	US10B WBX	SAR
2.0	EA	FLUSH BOLT	555	613		ROC
1.0	EA	DUST PROOF STRIKE	570	613		ROC
2.0	EA	FLOOR STOP	441H	613		ROC
2.0	EA	SPLIT ASTRAGAL	29310	DV		PEM
1.0	EA	DOOR CLOSER	1431	H	EB	SAR

D.2 HW GROUP AT DOORS AT LAUNDRY/EXIST. LANAI AND CORRIDOR/EXIST. LANAI

6.0	EA	HINGE	TA2714	4.5 X 4.5	US10B	MCK
1.0	EA	OFFICE LOCK	28-10G05	LG	US10B WBX	SAR
2.0	EA	FLUSH BOLT	555	613		ROC
1.0	EA	DUST PROOF STRIKE	570	613		ROC
2.0	EA	FLOOR STOP	441H	613		ROC
2.0	EA	SPLIT ASTRAGAL	29310	DV		PEM
1.0	EA	DOOR CLOSER	1431	H	EB	SAR
2.0	EA	AUTO. DOOR BOTTOM	4301DPKL	36"		PEM
1.0	EA	DOOR SEAL	S773D25			PEM

D.2 HW GROUP AT CORRIDOR

8.0	EA	HINGE	TA2714	4.5 X 4.5	US10B	MCK
1.0	EA	OFFICE LOCK	28-10G05	LG	US10B WBX	SAR
2.0	EA	FLUSH BOLT	555	613		ROC
1.0	EA	DUST PROOF STRIKE	570	613		ROC
2.0	EA	FLOOR STOP	441H	613		ROC
2.0	EA	SPLIT ASTRAGAL	29310	DV		PEM
1.0	EA	DOOR CLOSER	1431	H	EB	SAR

D.3 HW GROUP

6.0	EA	HINGE	TA2714	4.5 X 4.5	US10B	MCK
1.0	EA	OFFICE LOCK	28-10G05	LG	US10B WBX	SAR
2.0	EA	FLUSH BOLT	555	613		ROC
1.0	EA	DUST PROOF STRIKE	570	613		ROC
1.0	EA	WALL STOP (CONCAVE)	409	613		ROC
1.0	EA	FLOOR STOP	441H	613		ROC
2.0	EA	SPLIT ASTRAGAL	29310	DV		PEM
1.0	EA	DOOR CLOSER	1431	H	EB	SAR

SUSPENDED CEILING PANEL

CEILING PANEL SHALL BE 2 X 4 ARMSTRONG FIRE GUARD

SOLID SURFACE MATERIAL

PROVIDE CORIAN OR EQUAL